

DECLARATION

(To be given by the Agency along with Quotation)

I/we intend to supply the materials/execute the SITC to your office/at the location and shall comply the following :

1. Tender schedule and technical specification indicated.
2. This offer is valid for 30 (Thirty) days from the date of opening of the tender.
3. That we have not been debarred by any Government/Undertaking and our firm is not involved in any litigation or Arbitration with VITM, Bangalore.
4. That the rates quoted are not higher than the rates quoted for the same item to any Government/Undertaking.
5. That the bid submitted by us is properly sealed and prepared so as to prevent any subsequent alteration and replacement.
6. We have read and understood the terms and conditions mentioned in the Tender Document and undertake to comply them.

Sl No.	Description	To be filled by the bidder
1.	Name of the agency	
2.	Full Address of the agency	
3.	Contact Person Name with Mobile No.	
4.	PAN	
5.	GST No.	
6.	Nature of the entity (Limited Company, Partnership etc.)	

Tel./Fax/Mobile No. :

Email ID :

Signature & Seal :

Name of Authorized Signatory :

Place & Date :

OFFER FORM

Limited Tender Enquiry for Supply, Installation, Testing and Commissioning of 04 nos. of Hi-wall mounted inverter split Air-conditioner 5 Star rating at District Science Centre, Kalaburagi, Brahmapur, Kalaburagi, Karnataka 585101.

Sl. No	Description	Qty	unit	Rate	Amount
Part A - Supply of AC Machine					
1	Supply of Hi-wall mounted inverter split Air-conditioner 5 star rating, 2.0 Ton capacity single Ph 230 volt AC supply, one room unit, one condensing unit with copper condenser coil, eco friendly refrigerant gas, inverter rotary compressor and remote Including standard length (3 Mtrs) copper refrigerant pipe. 5 yeras compressor warranty, Stabiliser-Free Operation. Anti-Corrosive Protection, Blue Fins in ODU and Gold Fins in IDU, Stabiliser-Free Operation, Humidity Control (Dry Mode), Blue Star /Hitachi / Mitsubishi / O General/ Daikin	04	Nos.		
Sub Total Rs.					
GST @ 28% Rs.					
Total For Part A Rs.					
Part B- Allied Items / Installation Works					
1	Installation, Nitrogen pressure Testing and commissioning of Hi-wall mounted split Air-conditioner of different size as per Part A above	4	Nos		
2	Supply and fixing of G.I powder coated heavy-duty stand suitable for mounding of outdoor unit.	4	Nos		
3	Supply, installation, Testing & Commissioning of soft refrigerant piping. The brazing to be carried out with bleeding of nitrogen. The copper pipe to be insulated with 9mm/13mm thick insulation for pipe class 1 make Mandev, Uniflow, Totaline, PTP	8	Mtrs		
4	Supply and fixing of 25mm PVC pipes with necessary Insulation for drain cut to required lengths and installed complete with all necessary fittings like elbows, tees & reducers. Finolex, Prince, Supreme	20	Mtrs		
5	Supply and installation of 4 core 4.0 sq mm flexible copper wire between indoor and outdoor as required. Polycab, Finolex, KEI, Havells, V-Guard	15	Mtrs		
6	Supply and installation of Voltage Stabilizer 5 KVA, 15 Amps wall mounted 140-280 Volt Hi & Low auto cut, Digital display, Micro controlled and advanced Intelligent Time Delay System	4	Nos		
7	Supply and laying of UV resistant wrapping tape on refrigerant pipe. 2 inch width and 10 mtrs length. OEM recommended tape.	8	Rolls		
Sub Total Rs.					
GST @ 18% Rs.					
Total For Part B Rs.					
Grand Total for Part A & B Rs.					
Note:- Payment will be as per actual quantities executed at site.					

Signature, Date and Stamp of the Agency